

# The Competitive Difference

## Driveway Specification Sheet

All hardscape installations performed by TBI Unlimited, LLC are held to the highest industry standards. We provide you with this specification sheet so that you may further understand how, and why we are the fastest growing landscape/ hardscaping firm in South Jersey. When having TBI Unlimited, LLC install your hardscape you can rest assured that the following specifications will be adhered to at all times.

### 1)Excavation

- Soil will be excavated to a depth of 13" to 15" depending upon application.
- Depending upon scale of project and vehicle accessibility, excavation will be performed via hand, mini skid- steer or backhoe.

### 2) Compact Sub-grade

- Earth beneath paver surface will be thoroughly leveled by using laser levels
- Earth will then be compacted with vibratory plate compactors, or jumping jack compactors to achieve 98% Proctor Density.

### 3)Laying of Separation fabric

- Mirafi 500X geo-textile separating fabric will be laid upon previously compacted sub-grade, and will wrap all wall surfaces of excavated trench.
- Separating fabric provides as a barrier between soil and crushed concrete to eliminate settlement of concrete into soil.
- Mirafi 500X has a 50 year life expectancy.

### 4)Compaction of Aggregate Base

- A minimum of 10" of crushed concrete will replace the soil previously excavated from site.
- Crushed concrete will be laid and compacted in 2-3" intervals to achieve 98% Proctor Density.

### 5)Sand Setting Bed

- 1" Concrete sand will be screeded atop of compacted crushed concrete using 1" steel bars.
- Concrete sand acts as a setting base for pavers to rest in, and will compact to a 1/2"

### 6)Laying of Pavers

- Pavers selected by customer will be laid along pattern specified by contract.
- All cuts will be performed using diamond bladed wet/ dry saw.
- No paver joint/cut will exceed 1/4" gap.
- All corners will be miter cut to maintain cohesion throughout project.
- Paver joints will be swept with Polymeric joint stabilizing sand and compacted until full.
- Polymeric sand eliminates weed growth between pavers, as well as the emergence of ants, and erosion of sand.

### 7)Edge Restraint

- Pavers will be laterally reinforced with Brickstop.
- Brickstop is made of rigid, black plastic used to prevent lateral shift of pavers.
- Brickstop is anchored into aggregate base with 10" galvanized spikes.

TBI Unlimited, LLC.  
856.455.7832